

Project Info



08 / 08 / 2012



CC8 bulk rolls



1125sqm



3 longitudinal layers



Junction 12, M1
Bedfordshire, UK.



Costain & Carillion
Joint Venture



"Part of the M1 junction 12 project involved the lining of a 320 linear metre top of batter V ditch to prevent seepage and control water runoff. Concrete Canvas was specified over traditional concrete solutions for this project due to site limitations. The project was a success as the programme, originally scheduled for completion in 3 weeks, was completed in 5 days. Having used the product on previous projects, I knew the speed and ease of installation would be of great advantage to us."

Dale Flower Bsc (Hons)
J12 Roadworks Section Engineer
Costain Carillion Joint Venture

Completed lined ditch section



Batter prior to ditch excavation.



Graded ditch section with vegetation removed.



Lining the bottom of the transverse with the first longitudinal layer of CC



Lining the left side crest of the ditch



The edges of the CC were anchor trenched and backfilled after hydration.



Completed CC lined ditch section secured with ground pegs at 2m intervals.

