

Project Info



14 / 07 / 11



CC8™ Batched Rolls



100m²



Vertical layers



Andacollo, Chile



Polytrade



Surface recovery of a corroded concrete acid tank containing 17% concentrated sulphuric acid. Completed installation provided a renewed solid surface on which to install HDPE lining. Project completed in 8 hours by 4 people, compared to 21 days to construct a new tank. CC came into contact with acid during installation but this did not affect setting or performance.



Completed lined acid tank 9 hours after hydration.



Dilapidated concrete acid tank (in disrepair due to many years of exposure)



Recovering the tank ground level with graded earth



Start of CC installation (16:00hrs)



Completed installation (00:30 hrs)

